

October 4, 2011 - Bid award made to AAA Excavation, Inc for \$174,950.10.

ITEM #	ITEM DESCRIPTION	UNIT	QTY.	AAA Excavation		Associated Brigham Contractors		Geneva Rock Products		Rupp Trucking		Whitaker Construction	
				Unit Price	Extension	Unit Price	Extension	Unit Price	Extension	Unit Price	Extension	Unit Price	Extension
1	Traffic Control	LS	1	2,000.00	2,000.00	4,307.00	4,307.00	9,000.00	9,000.00	7,968.05	7,968.05	2,300.00	2,300.00
2	SWPPP Implementation	LS	1	2,000.00	2,000.00	901.00	901.00	3,000.00	3,000.00	7,968.05	7,968.05	1,800.00	1,800.00
3	Mill Existing Asphalt Pavement	SF	17,550	0.25	4,387.50	0.50	8,775.00	0.50	8,775.00	0.50	8,775.00	0.60	10,530.00
4	Replace Existing Asphalt	TON	520	85.00	44,200.00	144.00	74,880.00	103.00	53,560.00	163.18	84,853.60	140.00	72,800.00
5	Adjust Existing Manhole Cover	EA	7	225.00	1,575.00	307.00	2,149.00	1,000.00	7,000.00	450.00	3,150.00	650.00	4,550.00
6	Abandon and Remove Existing Hydrant	EA	3	400.00	1,200.00	182.00	546.00	1,000.00	3,000.00	800.00	2,400.00	650.00	1,950.00
7	Install Fire Hydrant Assembly	EA	4	4,090.00	16,360.00	5,596.00	22,384.00	8,000.00	32,000.00	4,390.60	17,562.40	5,200.00	20,800.00
8	Replace Existing Water Service From Main to Meter	EA	19	1,155.00	21,945.00	1,317.00	25,023.00	2,500.00	47,500.00	1,734.85	32,962.15	1,500.00	28,500.00
9	Install 16" by 8" Tapping Saddle	EA	1	2,746.00	2,746.00	2,811.00	2,811.00	2,500.00	2,500.00	3,219.04	3,219.04	2,200.00	2,200.00
10	Install 8" Gate Valve	EA	4	1,272.00	5,088.00	1,435.00	5,740.00	3,000.00	12,000.00	1,652.78	6,611.12	1,700.00	6,800.00
11	Install 8" PVC or DI Pipe	LF	728	25.80	18,782.40	90.00	65,520.00	79.00	57,512.00	52.48	38,205.44	43.00	31,304.00
12	Intall 12" DI Pipe	LF	21	41.20	865.20	115.00	2,415.00	300.00	6,300.00	106.22	2,230.62	120.00	2,520.00
13	Install 10" HDPE or 8" Fusible PVC by Boring	LF	110	100.00	11,000.00	147.00	16,170.00	170.00	18,700.00	97.92	10,771.20	200.00	22,000.00
14	Install 8" x 8" x 8" Tee	EA	1	527.00	527.00	642.00	642.00	1,500.00	1,500.00	768.94	768.94	450.00	450.00
15	Install 8" x 8" x 6" Tee	EA	4	448.00	1,792.00	345.00	1,380.00	1,500.00	6,000.00	690.83	2,763.32	450.00	1,800.00
16	Install 12" x 24" Tapping Saddle and 12" Gate Valve	EA	1	5,294.00	5,294.00	5,133.00	5,133.00	7,500.00	7,500.00	6,032.63	6,032.63	6,300.00	6,300.00
17	Install 12" x 12" x 12" Tee	EA	1	854.00	854.00	935.00	935.00	2,500.00	2,500.00	1,806.65	1,806.65	1,100.00	1,100.00
18	Not Used				-		-		-		-		-
19	Install 22.5 degree Flange x Flange Elbow	EA	1	938.00	938.00	762.00	762.00	1,500.00	1,500.00	616.52	616.52	1,100.00	1,100.00
20	Install Thrust Ring with Concrete Thrust Block	EA	1	250.00	250.00	702.00	702.00	2,500.00	2,500.00	350.00	350.00	2,800.00	2,800.00
21	Install Thrust Blocks	EA	14	100.00	1,400.00	446.00	6,244.00	200.00	2,800.00	150.00	2,100.00	150.00	2,100.00
22	Abandon Existing Connection to Main	EA	2	300.00	600.00	229.00	458.00	2,000.00	4,000.00	750.00	1,500.00	650.00	1,300.00
23	Abandon Existing Main	LS	1	300.00	300.00	104.00	104.00	2,500.00	2,500.00	1,000.00	1,000.00	4,000.00	4,000.00
24	Replace Existing Meter and Barrel	EA	11	968.00	10,648.00	1,017.00	11,187.00	1,500.00	16,500.00	1,510.25	16,612.75	1,500.00	16,500.00
25	Install 8" Gate Valve on Existing PVC Main	EA	1	2,436.00	2,436.00	2,591.00	2,591.00	3,500.00	3,500.00	2,222.23	2,222.23	3,000.00	3,000.00
26	Install Debris Cap For Pressure Zone Separation	EA	2	1,000.00	2,000.00	7.00	14.00	1,500.00	3,000.00	320.80	641.60	350.00	700.00
27	Install 12" MJ x MJ Butterfly Valve	EA	1	1,672.00	1,672.00	2,721.00	2,721.00	4,000.00	4,000.00	2,209.67	2,209.67	2,100.00	2,100.00
28	Install 8" x 8" x 8" x 8" Cross on Existing 8" PVC Intersection	EA	1	2,930.00	2,930.00	2,484.00	2,484.00	5,000.00	5,000.00	1,834.15	1,834.15	2,000.00	2,000.00
29	Install End Cap	EA	4	789.00	3,156.00	180.00	720.00	1,000.00	4,000.00	282.98	1,131.92	350.00	1,400.00
30	Replace Meter Barrel and Lid	EA	5	534.00	2,670.00	241.00	1,205.00	1,500.00	7,500.00	622.17	3,110.85	500.00	2,500.00
31	Replace 2" Meter	EA	2	2,467.00	4,934.00	2,660.00	5,320.00	3,000.00	6,000.00	2,593.64	5,187.28	3,100.00	6,200.00
32	Prepare "As-Built" Drawings	LS	1	400.00	400.00	63.00	63.00	1,000.00	1,000.00	250.00	250.00	250.00	250.00
TOTAL				174,950.10	174,950.10	274,286.00	274,286.00	342,147.00	342,147.00	276,815.18	276,815.18	263,654.00	263,654.00