

ENG 16046 400 NORTH RAISED PLANTER MEDIAN - Addendum 1

April 25, 2017

This Addendum is hereby attached to and made part of the Bid Request Documents. Each firm submitting a bid shall acknowledge receipt of this addendum and acceptance of all conditions contained herein by including the addendum number and date on the Proposal Sheet of the bid package.

ITEM 18 AGGIE BLUE PAVEMENT MARKING

- NEW Quantity 2425 sq ft. (Revised Bid Schedule attached and posted on web page)
- The Aggie Blue pavement marking shall be done in thermoplastic and will have to be color matched to get as close to Aggie Blue (PMS 539C) as possible, and only done on the 600 East intersection crosswalks.

ITEM 24 IRRIGATION SYSTEM

Recommendation from the Parks Division for the irrigation of the 400 North medians:

1. Separate water service to 300 North median and to 500 East median
2. Water service size will need to be 2-inch diameter to both medians
3. Backflow and valves as needed for both median irrigation systems
4. 2-inch sprinkler line to be installed at minimum 10 inches deep behind back of median curb on both sides of median (along south back of curb and north back of curb)
5. Half-circle pop-up spray heads to provide 9-foot radius installed to provide head-to-head coverage for both sprinkler lines for both medians
6. Spray heads for each sprinkler line in each median to be staggered in equal distance to provide uniform irrigation coverage
7. Each median irrigation system to include stop and waste for annual winterization
8. Flow sensor to be installed on both irrigation systems for both medians (flow sensor will require a Rain Bird specification for the controller, specified by Parks department)
9. Each median irrigation system valve to be wired to automated irrigation control timer and constructed for permanent installation and secured for authorized maintenance access only.

UDOT Clarifications – Upon award, the selected contractor will need to apply for an encroachment permit, provide a bond, and submit a traffic control plan through the online permit process.

BID SCHEDULE - Addendum 1

PROJECT: ENG 16046 400 North Raised Planter Median Construction

NOTE: Bidder agrees to perform all the work described in the CONTRACT DOCUMENTS for the following unit prices. Bid prices shall include sales tax and all other applicable taxes and fees.

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	TOTAL PRICE
1	Mobilization	LS	1		-
2	Traffic Control	LS	1		-
3	Survey	LS	1		-
4	Storm Water Pollution Prevention Plan	LS	1		-
5	Roadway Excavation (Plan Quantity)	CY	650		-
6	18" RCP Class III Storm Drain	LF	656		-
7	Catch Basin	EA	8		-
8	Reconstruct Roadway Monument	EA	2		-
9	Concrete Curb Type B5	LF	5,070		-
10	Plowable End Section	EA	4		-
11	Concrete Flatwork	SF	340		-
12	Remove Pavement Marking Paint	LF	4,138		-
13	Remove Pavement Message	EA	4		-
14	Pavement Marking Paint (4" Solid Yellow Line)	LF	5,200		-
15	Pavement Marking Paint (8" Solid White Line)	LF	945		-
16	Pavement Message (Turn Arrow)	EA	4		-
17	Thermoplastic Pavement Message (Turn Arrow)	EA	8		-
18	Aggie Blue Pavement Marking	SF	2,425		-
19	Median Sign	EA	4		-
20	No Left Turn Sign	EA	4		-
21	Geomembrane	SY	1,300		-
22	Topsoil (18")	SY	1,305		-
23	2" Water Meter	EA	2		-
24	Irrigation System	LS	1		-
25	Landscaping	LS	1		-

TOTAL BID

\$ _____ -

SIGNATURE OF PREPARER

COMPANY NAME
