



ENG 16046 400 NORTH RAISED PLANTER MEDIAN - Addendum 2

April 26, 2017

This Addendum is hereby attached to and made part of the Bid Request Documents. Each firm submitting a bid shall acknowledge receipt of this addendum and acceptance of all conditions contained herein by including the addendum number and date on the Proposal Sheet of the bid package.

ITEM 24 IRRIGATION SYSTEM - Clarifications to Addendum 1, Items 5, 8, and 9

5. Half-circle pop-up spray heads to provide 9-foot radius installed to provide head-to-head coverage for both sprinkler lines for both medians

9 ft. x 18 ft. nozzles (1.75 gpm) or U10 ft. nozzles (1 gpm); Rain Bird 1806 heads

8. Flow sensor to be installed on both irrigation systems for both medians (flow sensor will require a Rain Bird specification for the controller, specified by Parks department)

9. Each median irrigation system valve to be wired to automated irrigation control timer and constructed for permanent installation and secured for authorized maintenance access only.

Rain Bird ESP-LXME Controller 12-Station Base and LXMMPED metal cabinet

END OF ADDENDA