

500 North 600 East Waterline Replacement and Conduit Installation Questions & Answers

This information is hereby attached to and made part of the Bid Request Documents

January 25, 2017

1. Is an engineer's estimate available?

We do not have an engineer's estimate available.

January 31, 2017

2. There is a removal of curb and gutter but no item to replace?

The removal of curb is included for the installation of the power conduit. The reason for no item to replace the curb and gutter is because in May there will be a separate project to remove the remaining curb and gutter as part of an intersection improvement project. Include a minimal asphalt patch through curb to minimize erosion until next project begins.

3. Do we need to put a concrete collar around the water valves?

The water valves do not need a concrete collar, because of the future project.

4. Do we need to perform testing for the conduit trenches behind the curb?

All trenching needs to be compacted and tested at 95%.

5. Do we need to perform testing for the temporary asphalt patch?

The temporary asphalt does not need to be tested, however the sub-grade material will need to be tested per Logan City Standards.

6. Do we need to do compaction testing for the water services?

The trench for the water services will require compaction testing.

7. I only see 3 1" water service long and 3 1" inch water services short the bid items shows 6 per each.

The correct number of water services is 3 long services and 3 short services. The 6 per bid item is incorrect. See Addendum 1 for corrected Bid Schedule.

8. Can we close this intersection during construction and detour traffic?

The intersection can be completely closed during the construction process. The week of March 6-10 is spring break for USU.