

USU and Logan Cemetery Irrigation Pipeline

Questions and Answers

This information is hereby attached to and made part of the Bid Request Documents

Date	Question	Answer
1/25/18	1. On sheet 3, under the HMA notes, note 1 states that a prime coat is to be used. Are you meaning a tack coat? I have never seen a prime coat used on a project, it is applied directly to the UTBC. It is something that is no longer made in our region, last time I received a quote it was around \$30,000.00 with a minimum of 30 tons of oil that had to be purchased. It also has a short shelf life so its not something you can store for the next project. Let me know your thoughts on this.	The note should state TACK COAT and not prime coat.
1/25/18	2. The bid schedule reads 3" asphalt paving-100 Tons, and the plans call out for 6" thick asphalt patching. I was just wondering if you could clarify this?	This bid item is written incorrectly. A new bid schedule noting that 6 inches is required will be coming out. The new bid schedule will be issued per addendum sometime next week.
1/30/18	3. Has an estimated budget been established?	Engineers Estimate is \$480,000.00
2/2/18	4. Do you know the size of the Transite line located near station 7+00?	The size of the transite line is unknown. Assume 6-inch, if it is larger the City will negotiate.
2/2/18	5. Is there a permit fee schedule available from Logan city for the fees associated on this project?	Permits from the City are required for this project, however the fees will be waived.
2/2/18	6. In the Measurement and Payment on item #39 -C- Location where existing sprinkler systems have been disturbed shall have minimal area left open for repair by others. Is the contractor to repair these in item #19?	Irrigation pipes are to be repaired by the Contractor under Bid Item 19. References to leaving the irrigation crossing open are no longer in effect.
2/2/18	7. In the Measurement and Payment section of item #25-C- it calls for Clay Dams? I was unable to find a detail on these on the Logan City website.	No clay dams exist in this project, references to them should be ignored.

2/2/18	8. What item is the concrete paid for that goes on top of the Corrugated Metal “D Arch Overcast”?	Bid Item 38 has been revised. Scope of work has increased and unit for payment shall be a Lump Sum Basis.
2/6/18	9. Can you tell me what drawing bid item # 12 is on I can’t seem to find it. And is the corrugated arch under a drive approach ?	<p>Bid Item 12 is the 4” Storm Drain under the curb and gutter at approximately Sta. 4+35 enlarged on sheet 10.</p> <p>Corrugated arch on sheet 10 approximately Sta. 19+94. Revised bid schedule has this whole drive approach removed and replaced, including the CM arch.</p>
2/6/18	10. Does Logan City require Mega-Lug Restraints on MJ fittings?	Yes