

## Addendum #1

### 600 EAST 1200 NORTH TO 1150 NORTH SEWER LINE REPLACEMENT

March 12th, 2019

This Addendum is hereby attached to and made part of the Bid Request Documents. Each contractor submitting a bid shall acknowledge receipt of this addendum and acceptance of all conditions contained herein by including the addendum number and date on page 8 of the bid package.

---

#### **Bid Schedule:**

- Item 19 – New Line Item
- Item 20 – New Line Item

#### **Measurement and Payment:**

- Item 19 – New Line Item
- Item 20 - New Line Item

# BID SCHEDULE – Addendum 1

## 600 EAST 1200 NORTH TO 1150 NORTH SEWER LINE REPLACEMENT

Item	Description	Unit	Quantity	Unit Price	Item Price
1	Mobilization	Lump Sum	1		
2	Traffic Control	Lump Sum	1		
3	Prepare and Implement Storm Water Best Management Practices	Lump Sum	1		
4	Survey	Lump Sum	1		
5	Provide Quality Control Testing	Lump Sum	1		
6	Sewer By-Pass Pumping	Lump Sum	1		
7	Saw Cut Existing Asphalt	Lineal Feet	2350		
8	Remove Existing Asphalt	Square Feet	8750		
9	Trench Excavation	Tons	5700		
10	Install 8-Inch SDR 35 Sewer Line	Lineal Feet	720		
11	Reconnect Existing Sewer Lateral to Existing 8-Inch RCP	Each	1		
12	Reconnect Existing Sewer Lateral to 8-Inch SDR 35	Each	11		
13	Install 60-Inch Sewer Manhole	Each	3		
14	Install 48-Inch Sewer Manhole	Each	1		
15	Construct Granular Borrow	Ton	4200		
16	Construct Untreated Base Course	Ton	950		
17	Construct Hot Mix Asphalt, 4 Inches Thick	Square Feet	8,750		
18	Install Manhole Concrete Collar	Each	4		
19	Remove Existing 48-Inch Sewer Manhole	Each	4		
20	Remove Existing 8-Inch CMP Sewer Main	Lineal Feet	720		

TOTAL \$ \_\_\_\_\_

COMPANY NAME \_\_\_\_\_

SIGNATURE \_\_\_\_\_

# MEASUREMENT AND PAYMENT – Addendum 1

## PART 1 GENERAL

### 1.1 SECTION INCLUDES

1. General Description of Measurement and Payment

### 1.2 GENERAL ITEMS

1. Units of measurement are listed in the bid schedule.
2. See measurement and payment procedures in APWA Section 01 29 00.
3. Unit of Measure: Refer to the measurement and bid item that identifies the unit of measurement to be used for unit price items.

### 1.3 SCHEDULE OF BID ITEMS

19. REMOVE EXISITING 48-INCH SEWER MANHOLE
  - A. Measurement will be per each manhole removed.
  - B. The unit price to be paid for this item shall be considered compensation in full for all labor, materials and equipment required to remove and dispose of existing manhole.
20. REMOVE EXISITNG 8-INCH CMP SEWER MAIN
  - A. Measurement will be by lineal feet of existing pipe removed.
  - B. The unit price to be paid for this item shall be considered compensation in full for all labor, material and equipment required to remove and dispose of the existing 8-inch CMP sewer main.
  - C. This item also included the cost to disconnect the existing sewer laterals.
  - D. By-pass cost are included in item #6.