

Logan Center Street Project Main Street to 100 West

Addendum #2

June 26, 2019

This Addendum is hereby attached to and made part of the Contract Documents. Each Bidder shall acknowledge receipt of this addendum and acceptance of all conditions contained herein by entering the Addendum number and date in the space provided on Page 9 of the Bidding Documents.

All bids submitted without the signed acknowledgement of this Addendum will be rejected.

Item 1:

Replace the Bid Schedule with the following changes:

1. Changed quantity of Item 50, 18 Inch HDPE Pipe, to 2,478 Feet
2. Deleted Item 51, 18 INCH REINFORCED CONCRETE PIPE

Item 2:

Replace the Measurement and Payment with the following changes:

1. Changed Item 7, Site Clearing, Part B, to be:
 - B. Bid price covers cost for all labor, products, tools, equipment, transportation, services and incidentals to clear the project site. Includes removal of vegetation and trees (less than 20 inch circumference measured at a point 2 feet above the existing ground), and miscellaneous items less than 10 feet square.
2. Deleted Item 51, 18 INCH REINFORCED CONCRETE PIPE
3. Changed Item 55, UDOT Cleanout Box, 4 Ft X 4 Ft, Part B, to be:
 - B. Bid price covers cost of work and material in constructing and installing
 - 1) Cleanout Box – UDOT 2017 Standard Drawing CB 5. Meet the requirements of UDOT 2017 Standard Specification Section 02633.
 - 2) Solid Cover and Frame – UDOT 2017 Standard Drawing GF . Meet the requirements of UDOT 2017 Standard Specification Section 02635.

Item 3:

Replace the plan sheets with the following changes:

1. Sheets CU-101 to CU-103 – Changed all references to 18 inch reinforced concrete pipe to 18 Inch HDPE Pipe.
2. Sheet SG-101 – Modified note 16 to include salvaging the existing Gridsmart Camera system to Logan City.
3. Sheets LI-101 to LI-104 – Modified note 2 to read:
 2. THE IRRIGATION PLAN IS DIAGRAMMATIC TO NATURE, AND SOME DRAFTING LIBERTIES HAVE BEEN TAKEN TO MAINTAIN THE GRAPHIC CLARITY OF THE DRAWINGS. NO IRRIGATION EQUIPMENT, INCLUDING VALVES AND BOXES TO BE PLACED IN RAISED PLANTER BOXES. CONTRACTOR TO PROVIDE PROPOSED EQUIPMENT LOCATION TO THE ENGINEER FOR APPROVAL BEFORE INSTALLATION. THE CONTRACTOR SHALL INSTALL PIPING TO MINIMIZE CHANGES IN DIRECTION AND AVOID PLACEMENT UNDER LARGE TREES OR SHRUBS. REFER TO THE IRRIGATION EQUIPMENT SCHEDULE, INSTALLATION DETAILS, AND SPECIFICATIONS FOR EQUIPMENT AND ITS PROPER INSTALLATION.